

# Deployment discussion




**solar orbiter**




# Current timeline and corresponding blocks

## Block 1



## Block 2 : 12 min



**Deployment ANT Z**

## Block 3 : 23 min



**Deployment I-  
Boom**

## Block 4 : 23 min



**Deployment  
ANT X**

## Block 5 : 23 min



**Deployment  
ANT Y**

## Block 6 : 14 min



# Questions

## Block 1

First switch on

10-20 TM checks

- B 1. MOC : How will be checked the RPW TM? Which inputs (doc., soft, TM checks, etc.) are expected from RPW to support instrument monitoring and control during the operation?
- B 2. MOC : Is it 10-20 TM packets to checks (with several values) or only 10-20 values of TM parameters ?
- E 3. RPW : Which (specific) TM checks to add?
- E 4. RPW : Do we configure HK period at the very beginning ?
- E 5. How do we proceed to communicate to MOC the RPW on-board events and related action(s) to be performed (i.e, nothing to do versus switch off)? Is the table below ok ?

Produced TM packet	Continue	Switch off	Other
TM_DPU_TC_ACC_SUCCESS	X		
TM_DPU_TC_ACC_FAILURE		X	

# Questions

## Block 1

First switch on

10-20 TM  
checks

## Block 2 : 12 min

Config ANT Z  
« before depl. »

Wait 10  
min mini

Config ANT Z  
« during depl. »

Wait 1  
min

Deployment ANT Z

## Block 3 : 23 min

Wait 1  
min

Config ANT Z  
« after depl. »

Wait 10  
min mini

Config i-Boom  
« before depl. »

Wait 10  
min mini

Config i-Boom  
« during depl. »

Wait 1  
min

Deployment I-  
Boom

## Block 4 : 22 min

1. Minimum times required in order to have enough data to verify the well deployment. More is better !
2. How manage the timings if the deployment is postponed by 24 hours for example ? With this proposal, RPW stays in « during depl. » config for 24h !
3. Possibility to run the blocks XX min before the deployment, where XX corresponds to the blocks durations

# Our proposal

## Block 1

First switch on

10-20 TM  
checks

Block 2 : 1 min

Config ANT Z  
« before depl. »

Wait 10  
min mini

Block 3 : 1 min

Config ANT Z  
« during depl. »

Wait 1  
min

Deployment ANT Z

Block 4 : 1 min

Wait 1  
min

Config ANT Z  
« after depl. »

Wait 10  
min mini

Block 5 : 1 min

Config i-Boom  
« before depl. »

Wait 10  
min mini

Block 6 : 1 min

Config i-Boom  
« during depl. »

Wait 1  
min

Deployment I-  
Boom

Block 7 : 1 min

Wait 1  
min

Config iBoom  
« after depl. »

Wait 10  
min mini

Block 8 : 1 min

Config ANT X  
« before depl. »

Wait 10  
min mini

Block 9 : 1 min

Config ANT X  
« during depl. »

Wait 1  
min

Deployment  
ANT X

Block 10: 1 min

Wait 1  
min

Config ANT X  
« after depl. »

Wait 10  
min mini

Block 11: 1 min

Config ANT Y  
« before depl. »

Wait 10  
min mini

Block 12: 1 min

Config ANT Y  
« during depl. »

Wait 1  
min

Deployment  
ANT Y

## Block 13 : 14 min

Wait 1  
min

Config ANT Y  
« after depl. »

Wait 10  
min mini

Switch off